

Case 08-08 Maricopa County request the following revisions to section 301 be added to the proposed case revisions:

SECTION 301

SUBGRADE PREPARATION

Section 301 add the following:

301.2 Preparation of Subgrade: Subgrade preparation shall also include preparing subgrade to required line and grade for paved or unpaved shoulders, tapers, turnouts, and driveways, and all project locations where aggregate base and/or select material courses are used in accordance with the Project Plans.

301.2.1 The Contractor may use removed existing asphalt concrete and other existing bituminous roadway surfacing materials, originating on the project site, as embankment fill. All materials used shall be thoroughly crushed to sizes not exceeding four inches, or as approved by the Engineer. These asphalt/bituminous materials shall be placed not less than two feet below subgrade elevation.

Project earthwork quantities when included as separate contract pay items will include removed asphalt/bituminous material volumes, unless otherwise specified in the Special Provisions.

All unsuitable material and all excess material shall be disposed of in accordance with the requirements of Sections 205.2 and 205.6, respectively. When additional material is required for fill, it shall conform to Section 210.

301.3 RELATIVE COMPACTION:

Rock 6 inches or greater that becomes exposed due to scarification shall be removed from the scarified subgrade.

(E) Graded Shoulders 95 percent

301.7 MEASUREMENT:

Measurement for Subgrade Preparation will be by the square yard. The area to be measured will be the total accepted area of new asphalt or Portland cement pavement, including paved shoulders, tapers, and turnouts, and unpaved roadway shoulders. Measurement will also include driveways that are paved or are surfaced with aggregate base or select materials. The area under concrete curb and gutter, sidewalk, concrete driveway entrances, and concrete alley entrances will not be measured for this pay item.

Project earthwork quantities for Roadway Excavation, Borrow Excavation, and Fill Construction shall not be measured when they are all omitted from the fee schedule. Payment for the above earthwork items shall be included in the unit price for Subgrade Preparation.